

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

KCC PLET PER  
GPS  
NWSW

API Well Number: 15-009-20778-00-00

Spot: W2NESE

Sec/Twnshp/Rge: 31-18S-11W

1970 ~~1980~~ feet from S Section Line,

~~990~~ feet from E Section Line

Lease Name: KIMPLER B

1029 Well #: 1

County: BARTON

Total Vertical Depth: 3415 feet

Operator License No.: 31561

Op Name: HOFFMAN, CHRIS DBA C & K OIL COM

Address: 410 B ST PO BOX 531  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3414	1500	125 SX
SURF	8.625	249	0	150 SX

110.99

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/02/2009 8:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: CHRIS HOFFMAN

Company: C&K OIL COMPANY

Phone: (620) 786-8744

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/02/2009 12:00 PM

KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Sanded to 3300' - topped with 5 sxs cement.  
Cut casing at 1550' - pulled to 1050' - tied to casing and pumped 100 sxs cement with 200# hulls.  
Pulled to 600' - pumped 45 sxs cement with 100# hulls.  
Pulled to 300' - circulated cement to surface with 120 sxs cement and 100# hulls.  
Pulled casing - topped with 10 sxs cement - stayed full.

**Perfs:**

Top	Bot	Thru	Comments
3401	3415		ARBUCKLE

**INVOICED**  
DATE 3-31-09  
INV. NO. 2009061355

**RECEIVED**  
**MAR 13 2009**  
**KCC WICHITA**

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

MAR 05 2009

403 37 400  
 403 37 400  
 403 37 400

AL TIPTON #1 KIMPLER "B" 31-18-11W  
 BOX 519 HAYS, KS. C W/2 NE SE  
 CONTR DUKE DRILLING CO. CTY BARTON  
 GEOL J. C. MUSGROVE FIELD KIMPLER

E 1829 KB CM1/10/74 <sup>CARD</sup> ISSUED 3/7/74 IP P 36 BOPD N/W  
 ARB 3403-06 &  
 3470-73  
 API 15-009-20,778

+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM	
				8-5/8" 249/150SX, 5 1/2" 344/125SX
ANH		657	+1172	DST (1) 3104-90/30-30-30-30, 330' SW, BHP 637-611#, FP 52-214#
HEEB		2989	-1160	
TOR		3005	-1176	DST (2) 3404-15/30-30-30-30, 125' GIP, 80' OIL, 120' MO, BHP 1048-995#, FP 17-104#
DOUG		3020	-1191	
BR LM		3102	-1273	PF 3403-06, 3410-13, A 300, SWB 2 1/2 BOPH, A 700, SWB 5 BOPH, POP
LANS		3116	-1287	
ARB		3401	-1572	
RTD		3415	-1586	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS