

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20305-00-00
Spot: NWSESE Sec/Twnshp/Rge: 5-22S-14W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: MORRISON-LONG A Well #: 5
County: STAFFORD Total Vertical Depth: 3860 feet

Operator License No.: 31561
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM
Address: 410 B ST PO BOX 531
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3852	0	WITH 100 SX CMT
SURF	8.625	532		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2009 9:15 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: C & K OIL COMPANY Phone: (620) 786-8744

Proposed Plugging Method: BOTTOM THROUGH TBG PUMP 200# HULLS & 40 SX CMT. PERFORATE @ 900'. CIRCULATE CMT TO SURFACE.
125.45

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2009 5:17 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 3453'. PUMPED 15 SX GEL & 50 SX CMT W/200# HULLS. PERFORATED 4 1/2" @ 900'. PULLED TBG TO 917'. PUMPED 150 SX CMT & LOST CIRCULATION. WOC 4 HOURS. RAN TBG TO 917'. PUMPED 15 SX GEL & 100 SX CMT. LOST CIRCULATION. 2/27/09: TAGGED CMT @ 3360'. PULLED TBG TO 917' & PUMPED 300# HULLS - 50 SX 60/40 POZMIX 4% GEL & 50 SX THIXATROPIC. WOC 1 1/2 HOURS. TAGGED CMT AT 760'. AT 758' PUMPED 10 SX GEL, 300# HULLS, & 300 SX CMT. RAN OUT OF CMT. WOC 1 HOUR. PUMPED 50 SX CMT & CIRCULATED UP 8 5/8" X 4 1/2" ANNULUS. PULLED TBG & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3850	3860		
3818	3825		
3742	3750		
3481	3650		

INVOICED
DATE 3-31-09
INV. NO. 2009061355

RECEIVED
MAR 13 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

KCC WICHITA

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
MAR 12 2009
KCC DODGE CITY

Form CP