

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22365-00-00  
Spot: SESE Sec/Twnshp/Rge: 13-34S-14W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: BOUZIDEN Well #: 1  
County: BARBER Total Vertical Depth: 5020 feet

Operator License No.: 3532  
Op Name: CMX, INC.  
Address: 1551 N WATERFRONT PKWY STE 150  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2650		WITH 2 SX CMT
CIBP		3950		
PROD	4.5	5019	1000	WITH 250 SX CMT
SURF	8.625	346		WITH 240 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/25/2009 9:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 2650' WITH 5 SX CMT. PLUG AT 630' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.  
163.15

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/25/2009 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2650' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & SPOT PLUGS THROUGH 2 3/8" TBG. 1ST PLUG AT 630' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4744	4754		
4721	4741		

**INVOICED**  
DATE 3-31-09  
INV. NO. 2009061357

**RECEIVED**  
**MAR 13 2009**  
**KCC WICHITA**

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

**RECEIVED**

FEB 26 2009

**KCC DODGE CITY**

Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)