

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15605-00-00
Spot: NENENW Sec/Twnshp/Rge: 25-20S-12W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JACKSON Well #: 2
County: BARTON Total Vertical Depth: 3352 feet

Operator License No.: 31199
Op Name: JOINER, DON DBA D J OIL OPERATION
Address: 305 E 6TH
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3330		
PROD	5.5	3343	0	125 SX
SURF	8.625	265	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2009 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: DJ OIL OPERATIONS Phone: (620) 938-2943

Proposed Plugging Method: Ordered 525 sxs 60/40 pozmix - 4% gel - 550# hulls.
Casing leaks. High fluid level. Anhy 590'.
108.94

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2009 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso sanded off bottom and topped 5 sxs cement 03/03/2009 to 3100'.
RIH to tag cement plug - was gone 03/04/2009.
Log Tech set a CIBP at 3100'. Kelso ran in with a dump bailer and topped CIBP with 2 sxs cement.
RIH with tubing to 1450'. Copeland rigged to tubing and pumped 350 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in to circulate cement up 5 1/2" casing.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 100 sxs cement with 250# hulls mixed in to circulate cement up 8 5/8".
Shut in 8 5/8" - pumped 75 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3316	3320		
3276	3280		
3234	3240		
3198	3202		
3190	3194		
3154	3158		

INVOICED
DATE 3-31-09
INV. NO. 2009061359

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #35427.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

MAR 05 2009

ALPINE OIL & ROYALTY

#2

JACKSON

Arb
53

25-20-12W
NE NE NW

Contr. QUAKER DRILLING CO., INC.

BARTON

County

E 1815

Comm.

Comp.

1-14-49

IP

897 BOPD DEPTH 0

Tops	Depth	Datum
HCEB	2972	-1157
BR LM	3091	-1276
LANS	3109	-1294
ARB	3342	-1527
T.O.	3352	-1537

Casing

5" 3343 S.W. 20 BOPD/3 HRS
ACID 500

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

1815
1815
1815