

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

*KCCPKT*

API Well Number: 15-007-21589-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 15-32S-12W  
1651 feet from S Section Line, 4299 feet from E Section Line  
Lease Name: LONKER D Well #: 2  
County: BARBER Total Vertical Depth: 4875 feet

Operator License No.: 3372  
Op Name: DIXON ENERGY, INC.  
Address: 8100 E 22ND N BLDG 300, STE 200  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		WITH 5 SX CMT
PROD	4.5	4870	2700	WITH 150 SX CMT
SURF	8.625	429		WITH 350 SX CMT

Well Type: EOR UIC Docket No: E24250.1 Date/Time to Plug: 02/27/2009 12:30 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 4728' & 4 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

*158.44*

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2009 1:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*TAG BOTTOM @ 4056' W/BAILER. U-7 FORM SHOWS THAT BAKER AR-1 SNAP SET @ 3980'. RETAINER @ 4630' WHICH HAD BEEN STUNG INTO W/SEAL ASSEMBLY. SUSPECT BAD CASING OR JUNK LEFT IN HOLE.\*\* SET CIBP @ 3900' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN AND RUN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4778	4786		

**INVOICED**  
DATE 3-31-09  
INV. NO. 2009061360

**RECEIVED**  
MAR 13 2009

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

**KCC WICHITA**

District: 01

**RECEIVED**

MAR - 3 2009

**KCC DODGE CITY**

Signed

*Stephen J. Pfeifer*

(TECHNICIAN)