

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24926-00-00
Spot: W2E2SW Sec/Twnshp/Rge: 14-20S-14W
1400 feet from S Section Line, 1560 feet from W Section Line
Lease Name: BROCHER Well #: 1-14
County: BARTON Total Vertical Depth: 3699 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3699	2600	125 SX
SURF	8.625	805	0	175 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2009 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: HOLL, F.G., COMPANY LLC Phone: (620) 727-3410

Proposed Plugging Method: Ordered 290 sxs 60/40 pozmix - 4% gel - 500# hulls.
120.22

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2009 10:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/03/2009 - Sanded off and spotted 5 sxs cement on bottom.
Pulled casing to 1500'.
03/04/2009 - Pumped 150 sxs cement with 300# hulls.
Pulled to 850' - pumped 40 sxs cement with 100# hulls.
Pulled to 400' - pumped 95 sxs cement with 100# hulls.
Pulled casing out of hole and topped off with cement in cellar.

Perfs:

Top	Bot	Thru	Comments
3590	3598		
3576	3582		
3566	3572		
3544	3554		

INVOICED
DATE 3-31-09
INV. NO. 2009061361

RECEIVED
MAR 13 2009

Remarks: QUALITY WELL SERVICE-TICKET #2695.

KCC WICHITA

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

11/01/06
11/11/06
11/11/06

WILDCAT

F G HOLL COMPANY LLC
WICHITA KS 67206

14-20S-14W
1400' FSL & 1560' FWL, SEC

#1-14 BROCHER

site 2-3/4 S & 1-3/4 W OF GREAT BEND KS city: BARTON API 15-009-24926
cont: PETROMARK DRILLING #2 field WC (LIBERTY NE DISC)
geol: RENE HUSTEAD
dr date 04/07/2006 spd date 04/18/2006 drg comp 04/29/2006 card issued 09/25/2006 last revised 09/25/2006

ELV: 1887 KB, 1882 GL

tops.....	depth/datum
PBTD.....	3611 -1724
RTD.....	3700 -1813
NO TOPS RPTD	

IP status:
OIL, ARB, INTV NA, 07/07/2006
NOTE: CORRECTION 4/11/2006 - ORIG FR AS DUKE DRILLING AS CONTR
CSG: 8-5/8" 805 / 545 SX (ALT 1), 5-1/2" 3700
COMMENT: PROPOSED START 5/6/2006; MI & RURT 4/18/2006
NO CORES
8 DSTS TAKEN - DETAILS NA
TRGT ZN: HER, WINF, RED E, LKC, ARB (OIL/GAS), PTD 3675 (ARB), MICT - CO, PF (ARB) INTV NA, SWB DWN, GSO, POP, OIL WELL (POTENTIAL NOT RPTD), 7/7/2006 - TIGHT HOLE - NO OTHER INFO AVAILABLE - TEMP COMP 9/25/2006

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS