

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25147-00-00
Spot: SWSE Sec/Twnshp/Rge: 10-20S-14W
770 feet from S Section Line, 2200 feet from E Section Line
Lease Name: TAYLOR TRUSTS Well #: 1-10
County: BARTON Total Vertical Depth: 3700 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3699	2600	125 SX
SURF	8.625	800	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2009 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: HOLL, F.G., COMPANY LLC Phone: (620) 793-0915

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 500# hulls.
120.25

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded to 3480' - topped with 5 sxs cement.
Cut casing at 2600'.
Pulled casing to 1550' - tied to casing - pumped 155 sxs cement with 300# hulls.
Pulled to 850' - pumped 40 sxs cement with 100# hulls.
Pulled to 400' - pumped 100 sxs cement - circulated to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3585	3588		
3580	3582		
3570	3574		

INVOICED
DATE 3-31-09
INV. NO. 2009061361

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

F G HOLL COMPANY LLC
WICHITA KS 67206

#1-10 TAYLOR TRUST

10-20S-14W
770'FSL & 2200'FEL, SEC
KANSAS

City: BARTON
Site: 1-3/4 S & 2-1/2 W OF GREAT BEND KS
Field: MOSES NW

Spot: SE NW SW SE API 15-009-25147
Lat/Long: 38.32028 -98.85569

TEMP ABD

FR: 01/02/2008 Spd: 01/11/2008 Orig Cp: 01/22/2008 Issued: 12/15/2008 Revised: 12/15/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

TEMP ABD, 6/5/2008

Contr: DUKE DRILLING #7

Geol: RENE HUSTEAD

Elev: 1890 KB, 1882 GL, 1888 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

L HER	1741 +149
L WINF	1796 +94
L TOW	1865 +25
L FT RILEY	1904 -14
L FLORENCE	1955 -65
L B/FLORENCE	2002 -112
L KINNEY	2018 -128
L WREF	2049 -159
L CO GR	2069 -179
L CROUSE	2084 -194
L NEVA	2238 -348
L RED E	2296 -406
L AMER	2406 -518
L IND CV SD	2457 -567

L WAB	2476 -586
L ROOT	2583 -673
L STOT	2603 -713
L WILLARD	2629 -739
L TARK	2664 -774
L HOW	2803 -913
L SEVERY	2896 -1006
L TOP	2903 -1013
L HEEB	3138 -1248
L TOR	3159 -1269
L DOUG SH	3171 -1281
L BR LM	3236 -1346
L LANS	3249 -1359
L BKC	3510 -1620
L CONG	3516 -1626
L ARB	3548 -1658
L LANS H	3585 -1695
LTD	3700 -1810
RTD	3700 -1810

Csg: 8-5/8" 800 / 325 SX (ALT 1), 5-1/2" 3699 / 150 SX

Finds:

F G HOLL COMPANY LLC
WICHITA KS 67206

#1-10 TAYLOR TRUST

10-20S-14W
770'FSL & 2200'FEL, SEC
KANSAS
Side 2

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

COMMENT: MI & RURT 1/11/2008

NO CORES

DSTS TAKEN - DETAILS NA

Comp Info: TRGT ZN: ARB (OIL/GAS), PTD 3700

(ARB), MICT (3/28/2008) - CO, PF (ARB) 3570-3574,

W / 4 SPF, SPTD 500 GAL (10% ACETIC), AC 250

GAL (10% MIRA), NON-PROD, SQZ'D PFS W/25 SX

CMT, CO, PF (ARB) 3580-3582, 3585-3588, W / 4

SPF, SO, NAT, SI - EVAL, TEMP ABD 5/5/2008 - NO

OTHER INFO AVAILABLE - TEMP COMP 12/15/2008