

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19149-00-01
Spot: SWNESW Sec/Twnshp/Rge: 33-18S-11W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MUSENBURG A Well #: 3
County: BARTON Total Vertical Depth: 3402 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 513 W 6TH ST
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3394	0	100 SX
SURF	8.625	175	0	125 SX

Well Type: EOR UIC Docket No: E26569.1 Date/Time to Plug: 02/23/2009 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: K&N PETROLEUM, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
Perfed at 1550' and 625'.

110.57

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2009 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3033' - pumped 15 sxs gel - pumped 50 sxs cement with 100# hulls on bottom.
Pulled tubing to 1500' - pumped 200 sxs cement with 200# hulls - circulated cement to surface.
Pulled tubing - tied to casing - pumped 30 sxs cement.
Max. P.S.I. 300#. Shut in.
Tied to backside - pumped 30 sxs cement.
Max. P.S.I. 200#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3167	3169		CASING IS PARTE
3101	3107		

INVOICED

DATE 3-31-09

INV. NO. 2009061362

RECEIVED

MAR 13 2009

KCC WICHITA

Remarks: COPELAND CEMENTING COMPANY-TICKET #33118.

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

MAR 02 2009

I SERN DRILLING COMPANY #3 MUSENBERG 33-18-11W 53
 SW NE SW


Contr. _____ BARTON County

E 1813RB Comm. _____ Comp. 3-5-54 IP 60 BOPD
 PERM PMPG

Tops	Depth	Datum
HEEB	2961	-1148
BR LM	3078	-1265
LANS	3094	-1281
CONG	3382	-1569
ARB	3392	-1579
TD	3402	-1589

Casing
 8" 175
 5" 3394
 CO 3402: ACID 1500: 3½
 BOPH: PB 3180: PERF
 3150-54: ACID 4000; 1
 BOPH: PERF 3118-21; ACID
 1000: 1 BOPH:

BIEBERLE POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS