

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PLOT
PERCEPT
Die
4427

API Well Number: 15-185-22612-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 27-21S-12W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SHUMWAY A Well #: 5
County: STAFFORD Total Vertical Depth: 3590 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3580	2398	WITH 175 SX CMT
SURF	8.625	307		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2009 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3275' & 5 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.
116.68

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2009 12:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3275' & 5 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3579	3589		
3416	3420		
3399	3403		
3328	3332		

INVOICED
DATE 3-31-09
INV. NO. 2009061363

RECEIVED
MAR 13 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED
MAR - 3 2009
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)