

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCCPKT
OPS
1693-1650

API Well Number: 15-009-23917-00-00
Spot: SENWSW Sec/Twnshp/Rge: 33-16S-13W
1693-1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BRADSHAW Well #: 5
County: BARTON Total Vertical Depth: 3606 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3598	2600	150 SX
SURF	8.625	891	0	400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/06/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 200# hulls - 15 sxs gel.
117.20

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded to 3350' - topped with 5 sxs cement.
Cut casing at 2600'.
Pulled to 1550' - tied to casing - pumped 15 sxs gel - pumped 50 sxs cement with 100# hulls at 1550'.
Pulled casing to 900' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 550' - pumped 25 sxs cement.
Pulled to 150' - circulated to surface with 40 sxs.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3404	3406		

INVOICED
DATE 3-31-09
INV. NO. 2009061366

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35428.

Plugged through: CSG

District: 04


Signed Bruce Rodie
(TECHNICIAN) CM

MAR 11 2009

ALADDIN PETOLEUM CORPORATION
 809 PETROLEUM BLDG #5 BRADSHAW 33-16-13W
 WICHITA, KS 67202 SE NW SW

CONTR D.R. LAUCK OIL COMPANY CTY BARTON

GEOL JAY WARNER FIELD TRAPP



ELV 1942 KB SPD 4/12/85 CARD ISSUED 8/15/85 IP P 60 BOPD & WTR
ARB 3404-3406

LOG	Tops	Depth/Datum
TOP	2808-866
HEEB	3084-1142
TOR	3101-1159
DOUG	3114-1172
LANS	3176-1234
ARB	3400-1458
RTD	3606-1664

API 15-009-23,917
 8 5/8 " 891, 5 1/2 " 3598
 NO CORES OR DST'S
 MICT - CO, PF (ARB) 3404-06, AC 250G, SWB DWN & REC 10
 BFPH (70% OIL) / 1ST HR, 10 BFPH (80% OIL) / 2ND HR, POP, P
 60 BOPD & WTR

4110-111
 1871 13 300P
 1870-111

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS