

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22400-00-00
Spot: SENWSE Sec/Twnshp/Rge: 33-16S-13W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BRADSHAW Well #: 3
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3458	2227	150 SX
SURF	8.625	323	0	210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.
112.45

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2009 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded to 3350' - topped with 5 sxs cement.
Cut casing at 2227' - pulled to 1527' - pumped 150 sxs cement with 300# hulls.
Pulled casing to 700' - pumped 30 sxs cement.
Pulled to 250' - pumped 25 sxs cement.
Pulled to 150' - pumped 50 sxs cement - circulated cement to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3402	3408		

INVOICED

DATE 3-31-09
INV. NO. 2009061366

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAR 11 2009

