

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC PKT
PLUG PS*

API Well Number: 15-151-20361-00-00
Spot: SWSWNE S Sec/Twnshp/Rge: 21-27S-12W
3346 2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: EDWIN MAAS Well #: 1
County: PRATT Total Vertical Depth: 3200 feet

Operator License No.: 31629
Op Name: NASH OIL & GAS, INC.
Address: PO BOX 8747
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2615		WITH 2 SX CMT
PROD	4.5	2836	1016	WITH 100 SX CMT
SURF	12.75	191		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/24/2009 11:00 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: TONY NEW Company: MIDWESTERN WELL SERVICE, IN Phone: (620) 624-8203

Proposed Plugging Method: CIBP @ 2615' WITH 2 SX CMT. PERFORATE @ 690'. CIRCULATE CMT TO SURFACE OR PULL CASING TO 690' WITH 70 SX CMT. PLUG AT 330' WITH 70 SX CMT. PLUG AT 220' WITH 70 SX CMT.
104.00

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2009 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2615' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & RAN IN 2 3/8" TBG TO PLUG THROUGH. 1ST PLUG AT 690' WITH 15 SX GEL & 70 SX CMT. 2ND PLUG AT 344' WITH 70 SX CMT. 3RD PLUG AT 220' WITH 70 SX CMT. 4TH PLUG AT 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2665	2671		

INVOICED
DATE 3-31-09
INV. NO. 2009061368

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED
FEB 26 2009 *MP*

Signed Stephen J. Pfeifer
(TECHNICIAN)

KCC DODGE CITY