

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCCPT
per GPS
new*

API Well Number: 15-151-20461-00-00

Spot: N2N2SW

Sec/Twnshp/Rge: 16-27S-12W

2324 ~~2310~~ feet from S Section Line,

~~1320~~ feet from W Section Line

Lease Name: JOSSERAND

4179 Well #: 2

County: PRATT

Total Vertical Depth: 2725 feet

Operator License No.: 31629

Op Name: NASH OIL & GAS, INC.

Address: PO BOX 8747
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 2 SX CMT
PROD	4.5	2724	1000	WITH 100 SX CMT
SURF	8.625	309		WITH 300 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 02/25/2009 3:00 PM

Plug Co. License No.: 5112

Plug Co. Name: MIDWESTERN WELL SERVICE, INC.

Proposal Rcvd. from: TONY NEW

Company: MIDWESTERN WELL SERVICE, IN Phone: (620) 624-8203

Proposed Plugging Method: CIBP @ 2600' & 2 SX CMT. PERFORATE @ 620' CMT TO SURFACE OR PULL CASING TO 620' PUMP 50 SX CMT. PLUG AT 330' WITH 50 SX CMT.

88.56

Plugging Proposal Received By: STEVE DURRANT

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/25/2009 4:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PLUG THROUGH 4 1/2" CASING. 1ST PLUG AT 620' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2680	2684		

INVOICED
DATE 3-31-09
INV. NO. 2009061368

RECEIVED
MAR 13 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

KCC WICHITA

District: 01

RECEIVED

FEB 26 2009

KCC DODGE CITY

Signed

Stephen J. Pfeifer

(TECHNICIAN)