

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-22173-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 10-31S-33W
1216 feet from S Section Line, 1049 feet from E Section Line
Lease Name: BEELMAN Well #: 11-P10-31-33
County: SEWARD Total Vertical Depth: 629 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

35.00

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 03/11/2009 12:00 AM
Plug Co. License No.: 33784 Plug Co. Name: TRINIDAD DRILLING LIMITED PARTNERSHIP
Proposal Rcvd. from: MARK NEELAND Company: PRESCO WESTERN Phone: (303) 444-8881

Proposed Plugging Method: PUMP 50 SX CMT AT 600'. WOC 4 HOURS. TAG PLUG. CIRCULATE CMT FROM TOC RO 0' W/CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 03/11/2009 3:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

LOST CIRCULATION @ 622'. MARKED HOLE WITH STEEL BAR. 1ST PLUG RIH W/DRILL PIPE AND SPOT 50 SX CMT. WOC 4 HOURS & TAG WITH DRILL PIPE. 2ND PLUG TAGGED CMT AT 530'. PUMPED 400 SX CMT. DID NOT CIRCULATE. WAIT ON CMT 4 HOURS & TAG. 3RD PLUG TAG TOC @ 422'. PUMP 200 SX CMT. CIRCULATE CMT TO SURFACE. 20 BBLs TO PIT. 4TH PLUG CIRCULATED 30 SX CMT IN MOUSEHOLE. 5TH PLUG CIRCULATED 20 SX CMT IN RATHOLE.

INVOICED
DATE 3-31-09
INV. NO. 2009061370

Remarks: USED 60/40 POZMIX 4% GEL 2% CC BY ALLIED.

Plugged through: DP

RECEIVED
MAR 13 2009
KCC WICHITA

District: 01

Signed

Steve Durrant
(TECHNICIAN)

RECEIVED

MAR 12 2009

KCC DODGE CITY