

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-16-1973
AUG 16 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address P. O. Box #352, Russell, Kansas.

Lease Name Schaben Well No. 1

Location CSE-NW Sec. 3 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 10:30 AM Day 14 Month 8 Year 1973

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated with 140 Sx.

3799'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 3744'. Top perforations from 3628' to 3632'.

Pushed plug to 3600', sanded on top of plug to 3580' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2900' plus) and squeezed well initially with 5 sacks hulls and 14 sacks gel and followed with 110 Cu. Ft. cement from 850' to 525' then 7 sacks gel from 525' to 245' and followed with 30 Cu. Ft. cement from 245' to 170' then 4 sacks gel from 170' to 20' and finally 10 Cu. Ft. cement from 20' to bottom of cellar.

Maximum pump-in pressure-400#. Final shut-in pressure-250* (Cementing by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Daniels
Well Plugging Supervisor

INVOICED

DATE 8-16-73

INV. NO. 7783-W