

15-195-20244-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
7-30-1973  
JUL 30 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address P. O. Box #352, Russell, Kansas.

Lease Name Schaben Well No. 2

Location CSE-NE Sec. 3 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3745'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 11:30 AM Day 23 Month 7 Year 1973

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 625'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 110 Cu. Ft. cement  
thru DP from 850' to 525'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 7-30-73

INV. NO. 7698-60