

15-195-21058-00-00

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-195-21,058-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name F. & M. OIL COMPANY, INC.

Complete Address 505 UNION CENTER, WICHITA, KANSAS, 67202

Lease Name COMEAU Well No. #2

Location NE-SW-NW Sec. 6 Twp. 11 Rge. 23 (East)(West)

County TREBO Total Depth 3950 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor UNION DRILLING CO. INC. [LYLE BASON]

Address 505 UNION CTR. BLDG. WICHITA, KANSAS. License No. _____

Operation Completed: Hour: 8:00 AM Day: 12th Month: AUG. Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 292 FT. SP. CAS. w/ 175ST COMMON-2% GEL-3% CA-CL.

ORDERED 140ST 50/50 FORMIX 4% GEL.-3% CA-CL. & 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST Plug @ 960 FT w/ 80ST CMT.

2ND Plug @ 300 FT w/ 40ST CMT.

3RD Plug -> SOLID BRIDGE
HULL'S - 7446 @ 40 FT TO 0 w/ 10ST CMT.

10ST IN RAT HOLE (CIRCULATE)

CEMENTED BY SHN CMT.

Amount of Surface Casing: 292 FT.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
8-23-1982
AUG 25 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 9-8-82

INV. NO. 1013-W