

15-195-20165-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-31-1970
JUL 31 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Walker Well No. 1

Location SW-NE-SW Sec. 7 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling, Incorporated,

Address 339 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 7:15 PM Day 28 Month 7 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 100 Sx. cement thru
DP from 925' to 600'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/31/70
INV. NO. 2318-W