

15-195-20180-00-00

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-9-1971
JUN 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 117 Cameron Building, Oklahoma City, Oklahoma. 73106

Lease Name Staggers Well No. 1

Location SE-SW-SW Sec. 8 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 AM Day 1 Month 6 Year 1971

The above well was plugged as follows:

n 208'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru
DP from 875' to 550'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 6-9-71

INV. NO. 3827-W