

15-195-19034-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name John P. Jennings,

Complete Address: Union Center, Wichita, Kansas.

Lease Name Galloway Well No. 1

Location SE-SW-SW Sec. 10 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Glenn and Smith Pipe Pulling Company,

Address: 204 E. 6th Street, Ellinwood, Kans. License No. 396

Operation Completed: Hour 1:15AM Day 15 Month 6 Year 1967

The Above well was plugged as follows:

210'--7" OD Surface pipe, cement circulated with 115 Sx.

3709'--4 1/2" Production casing cemented with 150 Sx. No plug back, no perforations. Open hole completion.

Sanded well back to 3700' and set 3 Sx. cement with dump bailer. Pulled

4 1/2" casing and squeezed well with 20 sacks gel, using 3 sacks hulls in in-

itial gel and followed with 50 Sx. cement. Maximum pump-in pressure 400#.

Final shut-in pressure 150#. (Recovered 2700' 4 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dichel
Well Plugging Supervisor

DATE 6/19/67
INV. NO. 5416-W