

15-195-20140-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Company & Franks Petroleum, Incorporated.

Complete Address P. O. Box #867, Magnolia, Arkansas.

Lease Name Heckman Well No. 1

Location SW-SE-SE Sec. 11 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3558'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling Company, Incorporated.

Address 1014 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:00 AM Day 2 Month 11 Year 1969

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 615'.

Circulated hole with heavy mud, pulled DP to 840' and displaced 100 Sx. cement thru DP
from 840' to 515'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from 245' to
185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/6/69
INV. NO. 783-U

Signed: A. L. Nichols
Well Plugging Supervisor