

15-195-00371-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SE SW

SEC. 13 TWP. 11 RGE. 23

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Carpenter

Operator B & R Drg Co Address Russell, Kans

Field \_\_\_\_\_ County Trego

Total Depth 4050 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 150' circula ed with cement - 5 1/2" at 3704'

with 75 sax cement behind - Lane Wells plugs to 3586'

perforated at 3576'.

Filled with chat to 3555', set 4 sax cement with dump bailer

pulled 1500' 5 1/2", filled with mud to 250', set rock and

15 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar.

**PLUGGING**  
FILE SEC 13 T 11 R 23  
BOOK PAGE 53 LINE 21

10-20-1952  
OCT 20 1952  
CONSERVATION DIVISION  
Wichita, Kansas

*Eldon Perry*  
District Conservation Agent

Date 10-15-52