

15-195-20138-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Carpenter Well No. 2

Location CSW-SW Sec. 13 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3794'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor B & B Drilling, Incorporated,

Address 207 Petroleum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:30 PM Day 2 Month 10 Year 1969

The above well was plugged as follows:

231'--8 5/8" Surface casing, cement circulated with 145 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 100 Sx. cement thru
DP from 825' to 500'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/7/69
INV. NO. 599-W

Signed: A. L. Nichols
Well Plugging Supervisor