

15-195-01486-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO: _____

LOCATION CW $\frac{1}{2}$ W $\frac{1}{2}$ NE

SEC. 26 TWP. 11 RGE. 23

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Howatt

Operator Smoky Hill Oil Co Address Russell, Kans

Field _____ County Trego

Total Depth 3666 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3663' with 100 sax
cement behind Set 5 sax cement in bottom with dump bailer - bridged
hole at 3100' set 5 sax cement with dump bailer - pulled 2800' 5 1/2"-
filled hole with mud to 240', set rock bridge and 15 sax cement -
mud to 35', set rock and 10 sax cement to bottom cellar.

District Conservation Agent

Date 3-25-52

RECEIVED
APR 1 1952

PLUGGING
FILE SEC 26 TWP 11 RGE 23
BOOK PAGE 2 LINE 2