

15-065-20160-0001

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
5-20-74
MAY 20 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated.

Complete Address P. O. Box #922, Great Bend, Kansas.

Lease Name Moore Well No. 2

Location SE-SW-SW Sec. 27 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4110'

Abandoned Oil Well Gas Well Input Well / SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Halliburton Services,

Address Drawer "D", Hill City, Kansas. License No.

Operation Completed: Hour 3:30 PM Day 16 Month 5 Year 1974

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated.

4109'--4 1/2" casing cemented on bottom with 250 Sx. Top perforations from 3906' to 3910'.

Sanded well back to 3850' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing

and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110

Cu. Ft. cement from 1250' to 925' then 17 sacks gel from 925' to 250' and followed

with 30 Cu. Ft. cement from 250' to 175' then 4 sacks gel from 175' to 25' and finally

10 Cu. Ft. cement from 25' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickels

Well Plugging Supervisor

INVOICED

DATE 5/21/74INV. NO. 9159-W