

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Monarch Oil and Gas Company,

Complete Address: 1005 Wichita Plaza, Wichita, Kansas.

Lease Name Pettett Well No. 1

Location SE-SE-SE Sec. 25 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drilling Company, Incorporated,

Address: 500 Bitting Building, Wichita, Kans. License No. _____

Operation Completed: Hour 9:00AM Day 17 Month 7 Year 1967

The Above well was plugged as follows:

207'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1675' to 1885'.

Ran DP to 1910', circulated hole with heavy mud and displaced 111 Sx.
cement thru DP. Pulled DP. to 210' and displaced 20 Sx. cement thru DP.
Pulled DP., set plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

Jul 21 1967
7-21-67

CONSERVATION DIVISION
Wichita, Kansas

Signed: A. A. Nichols
Well Plugging Supervisor

INVOICED

DATE 7/21/67
INV. NO. 6008-u

CP-3