

40

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
8-5-69
AUG 5 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Pettett Well No. 1

Location NW-SE-SW Sec. 25 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:15 AM Day 2 Month 8 Year 1969

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/5/69

INV. NO. 243-W

Signed: W. L. Nichols
Well Plugging Supervisor