

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01000-00-00
Spot: SESESW Sec/Twnshp/Rge: 28-9S-24W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: HOETING Well Number: 5-1
County: GRAHAM Total Vertical Depth: 4110 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 8/33.58
Surface Casing: Size 8.625 feet: 205 150 SX CMT
Production: Size 5.5 feet: 4107 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/17/2002 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing squeeze at 1432' with 100 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/17/2002 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perf casing at 1100' and 2100'.
RIH with tubing to 2200'.
Spotted 200 sxs cement with 400# hulls to circulate cement at surface.
POOH with tubing and squeezed 5 1/2" casing with an additional 50 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.
R.U. Cementers to 8 5/8" S.P.
Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
9-23-02
SEP 23 2002
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS DREILING #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

9-24-02

INV. NO.

2003060543

SEP 20 2002

13310VMI
 BT40
 201.00

MJRF IN DRILLING

#1 DRILLING

28-9-21W
 SE SE SW

Contr. MJRF IN DRILLING

GRAHAM

County

E. 2531 RBComm

Comp 6-28-57

IP 98 BOPD/KC

PHY POT

| Tops | Depth | Datum |
|------|-------|-------|
| HEEB | 3831 | -1300 |
| LANS | 3864 | -1333 |
| B/KC | 4094 | -1563 |
| T.D | 4110 | -1579 |

Casing
 8" 205
 5" 4107
 DST 3866-83/1 HR, 120' O & GCM, 60' HO & GCM, 180' MCO, 420' GSY 0, 300' SW, BHP 1090#
 DST 3893-3902/1 HR, 315' SW, BHP 1150#
 DST 3906-10/1 HR, 300' SW, BHP 1275#
 DST 3990-4005/1/2 HR, 12' MUD, BHP 1125#
 DST 4018-35/1 HR, 70' HO & GCM, 60' OIL BHP 925#
 DST 4058-80/45", 12' MUD
 DST 4049-80/1 HR, 450' G, 30' H OCM, 10' MCO, 20' W, BHP 1275#
 PERF 3/4045-48: TST 4 BOPH, TR WTR: 3/4026-31: TST 4 1/2 BOPH/6 HRS ACID 2500: TST 20 BOPH

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

GLEN DALE SW POOL OPENER