

15-065-20352-0000

Form CP-3
Rev. 6-4-68

KANSAS

JL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
8-5-70
AUG 5 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don Pratt Oil Operations,
Complete Address Drawer #370, Hays, Kansas.
Lease Name Hoeting Well No. 2
Location NE-SW-NW Sec. 28 Twp. 9 Rge. (E) (W) 24
County Graham Total Depth 4095'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor L. J. Dreiling & Sons, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 4:00 AM Day 1 Month 8 Year 1970

The above well was plugged as follows:

273'-- 8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 100 Sx. cement thru
DP from 1240' to 915'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. R. Nichols*
Well Plugging Supervisor

INVOICED
DATE 8/6/70
INV. NO. 2330-4