

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
4-30-73  
APR 30 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Don E. Pratt,  
Complete Address P. O. Box #370, Hays, Kansas.  
Lease Name Englebert Well No. 1  
Location NE-SE-NW Sec. 29 Twp. 9 Rge. (E) (W) 24  
County Graham Total Depth 3890'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center Building, Wichita, Kansas. License No.         
Operation Completed: Hour 9:30 PM Day 27 Month 4 Year 1973

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement  
thru DP from 1225' to 900'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/30/73  
INV. NO. 7305-W

Signed: R. L. [Signature]  
Well Plugging Supervisor