

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-26-73
NOV 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Bieker Well No. 2

Location NW-SW-SE Sec. 30 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4132

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 12:30 PM Day 17 Month 11 Year 1973

The above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 200 Sx.

4127'--5 1/2" casing cemented on bottom with 125 Sx. Top of perforations @ 3963'.

Pushed plug to 3900', sanded back to 3850' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (1120') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1275' to 950' then 17 sacks gel from 950' to 270' and followed with 30 Cu. Ft. cement from 270' to 195' then 4 sacks gel from 195' to 35' and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maximum pump-in pressure-550#. FSIP-200#. (Mudding & cementing by Sun Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. O. J. J. J.
Well Plugging Supervisor

DATE 11/29/73
INV. NO. 8216-W