

15-045-20459-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
11-26-73
NOV 26 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Reynolds Well No. 2

Location 21² RC NW NE-SE-SW Sec. 30 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4115'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:45 AM Day 16 Month 11 Year 1973

The above well was plugged as follows:

231'--8 5/8" Surface casing, cement circulated with 175 Sx.
4114'--4 1/2" Production casing cemented on bottom with 175 Sx. Top of perforations @ 3739'.

Pushed plug to 3700', sanded back to 3650' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1130') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1275' to 950' then 17 sacks gel from 950' to 270' and followed with 30 Cu. Ft. cement from 270' to 195' then 4 sacks gel from 195' to 35' and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maximum pump-in pressure-1200#. FSIP-200#. (Mudding & cementing by Sun Cementing Inc.).

INVOICED
I hereby certify that the above well was plugged as herein stated.

DATE 11/29/73
INV. NO. 8215-W

Signed: [Signature]
Well Plugging Supervisor