

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
7-29-63
JUL 29 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Co. & Time Petroleum Co.,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Critchfield Well No. 1

Location CSE-NW Sec. 33 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4100

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Empire Drilling Co.,

Address: 650 4th Nat'l Bank Bldg. Wichita, License No.

Operation Completed: Hour 10:30PM Day 25 Month 7 Year 1963

The Above well was plugged as follows:

156'--8 5/8" Surface pipe, cement circulated with 85 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx cement
thru DP. Heavy mud to 150', set plug with 1/4 Sx hulls and displaced 20 Sx
cement thru DP. Heavy mud to 40', set plug with 1/2 Sk hulls and 10 Sx
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. T. Scholtz
Well Plugging Supervisor

DATE 7/29/63

INV. NO. 7488-U