

15-065-20654-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-8-74  
MAR 8 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Delta Western Company & George Reed.  
Complete Address 1223 Union National Building, Wichita, Kansas.  
Lease Name Critchfield Well No. 4  
Location CNW/4 Sec. 33 Twp. 9 Rge. (E) (W) 2h  
County Graham Total Depth 4125'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor C & G Drilling Company.  
Address 1107 Union National Bldg., Wichita license No.         
Operation Completed: Hour 5:45 AM Day 5 Month 3 Year 1974

The above well was plugged as follows:

299'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1025'.  
Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement  
thru DP from 1250' to 925'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Dehals*  
Well Plugging Supervisor

INVOICED

DATE 3/12/74

INV. NO. 8722-W