


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County, Sec. 10 Twp. 11S Rge. 18W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines SE SW NE
Lease Owner Davis Bros. - Transit Corporation
Lease Name Meistrell A Well No. 1
Office Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 15, 1961
Application for plugging filed November 15, 1961
Application for plugging approved November 15, 1961
Plugging commenced November 15, 1961
Plugging completed November 15, 1961
Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	229'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 150', set plug, cemented with 20 sacks of cement
Filled hole with heavy drilling mud to 180', set plug, cemented with 20 sacks of cement
Filled hole with heavy drilling mud to 40', set plug, cemented with 10 sacks of cement to bottom of cellar

12-7-1961
DEC 7
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Paul E. Gathers

(Address) _____

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1961

My commission expires March 10, 1965

Debra M. Anderson
Notary Public.



15-051-01322-00-00

DRILLER'S WELL LOG

Davis Bros. - Transit Corporation

Meistrell "A" # 1 well located in
SE SW NE, Section 10-11S-18W,
Ellis County, Kansas

Commenced: November 2, 1961
Completed: November 15, 1961
Elevation: 1905 KB

Casing: 8 5/8" @ 229'
Cemented w/130 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Summary of Formations</u>	
Surface clay	0	25	Anhydrite	1207
Sand	25	35	Topeka	2888
Shale and shells	35	85	Heebner	3108
Sand	85	105	Toronto	3132
Shale and shells	105	130	Lansing	3150
Shale	130	229	Base of K.C.	3391
Shale and shells	229	580	Conglomerate	3420
Sand	580	730	Simpson Sand	3465
Shale	730	790	Simpson Dolomite	3476
Sand	790	885	Arbuckle	3494
Shale	885	920		
Shale and Pyrite	920	1075		
Red bed shale	1075	1207		
Anhydrite	1207	1236		
Shale	1236	1805		
Lime w/shale	1805	1900		
Lime w/shale streaks	1900	2025		
Shale	2025	2135		
Lime and shale	2135	2740		
Shale	2740	2888		
Lime	2888	2910		
Lime and shale	2910	2950		
Lime	2950	3105		
Heebner shale and lime	3105	3153		
Lime and shale	3153	3188		
Lime	3188	3296		
K.C. lime	3296	3336		
Lime	3336	3390		
Lime and shale	3390	3415		
Lime	3415	3420		
Conglomerate	3420	3466		
Simpson shale	3466	3494		
Arbuckle	3494	3503 TD		

RECEIVED
STATE COMMISSION
12-7-1961
DEC 7 1961
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing to be a true and correct Driller's Log of the formations encountered in the above well.

Subscribed and sworn to before me
this 15th day of December, 1961

TRANSIT CORPORATION

By Paul E. Gathers

My commission expires March 10, 1965

Walter M. Anderson
Notary public

