


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 28 Twp. 9 S Rge. 25 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
N/2 SW NE

Lease Owner Leith Operations
Lease Name SAUER Well No. 2
Office Address 427 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Dry hole
Date Well completed June 7, 1977
Application for plugging filed (verbally) June 7, 1977
Application for plugging approved (verbally) June 7, 1977
Plugging commenced June 7, 1977
Plugging completed June 7, 1977

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug at 900' with 70 sacks
2nd plug at 200' with 20 sacks
3rd plug at 40' with 10 sacks

Plug was down at 5:30 p.m., June 7, 1977


RECEIVED
STATE CORPORATION COMMISSION
6-21-77
JUN 21 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack Partridge
801 Union Center, Wichita, Kansas 67202
(Address)



20th day of June, 1977
Sandra Richman
Sandra Richman Notary Public

My commission expires July 21, 1979.

CONTRACTOR'S WELL LOG

OPERATOR: Leith Operations
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SAUER #2
 LOCATION: N/2 SW NE Section 28-9S-25W
 Graham County, Kansas
 SPUD DATE: June 2, 1977
 COMPLETION DATE: June 7, 1977

0	103	Surface clay
103	178	Sand
178	232	Shale
232	2218	Shale & sand
2218	2254	Anhydrite
2254	2810	Shale
2810	3000	Shale & lime
3000	3203	Shale
3203	3500	Shale & lime
3500	3668	Lime & shale
3668	3838	Shale & lime
3838	3952	Lime & shale
3952	4135	Lime
	4135	Rotary Total Depth

Spud hole at 12:15 p.m. 6-2-77. Drilled 232' of 12 1/4" hole. Ran 6 joints of 8-5/8" surface casing. Set at 231' K.B. Cemented with 175 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 5:30 p.m. 6-2-77.

T.D. 4135'. Set 1st plug at 900' with 70 sacks, 2nd plug at 200' with 20 sacks, 3rd plug at 40' with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 5:30 p.m. 6-7-77. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:
 Anhydrite 2218'
 B/Anhydrite 2254'


RECEIVED
 STATE CORPORATION COMMISSION
 JUN 21 1977
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SAUER #2, N/2 SW NE Section 28-9S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
 Jack L. Partridge, Ass't. Sec.-Treas.



Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of June, 1977.

My commission expires July 21, 1979.

Sandra Richman
 Sandra Richman, Notary Public