

15-065-00512-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 28 Twp. 9S Rge. 25W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Burch Drilling Co., Inc.

Lease Name Sauer Well No. 1

Office Address 1011 Union Center, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-9-58 19

Application for plugging filed 5-9-58 19

Application for plugging approved 5-9-58 19

Plugging commenced 5-9-58 19

Plugging completed 5-9-58 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation Depth to top Bottom Total Depth of Well 4080 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	225'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug @ 500' w/ 25 sx.

Set 2nd plug @ 225' w/ 15 sx.

Set 3rd plug @ 40' w/ 10 sx.

RECEIVED
STATE CORPORATION COMMISSION

5-24-58
MAY 24 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burch Drilling Co., Inc.

Address 1011 Union Center, Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Earl M. Burch (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl M. Burch
1011 Union Center, Wichita
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 19 58

My commission expires July 27, 1960

Gunny Harrison
Notary Public.



PLUGGING
FILE SEC 28 T 9 R 25W
BOOK PAGE 100 LINE 32

WELL LOG

Burch Drilling Co., Inc.
#1 Sauer
NW NW SE, 28-9S-25W
Graham County, Kansas

8 5/8" set @ 225'w/150 sx.
Elevation: 2565' KB
Comm.: 4-29-58
Comp.: 5-9-58
D & A

225 Clay & Sand
1680 Shale & Shells
2230 Shale & Lime Streaks
3780 Lime & Shale
4035 Lime
4080 Lime & Shale

4080 RTD

Heebner: 3805
Toronto: 3828
Lansing: 3844
BKC: 4074

DST #1 3814-3851. 30 minutes
Rec. 18' mud. All pressures
0#, except FBHP 1060#.

DST #2 3883-3900. 1 hour
Rec. 858' saltwater with few
specks oil. IBHP 1400#,
IFP 50#, FFP 410#, FBHP (30
min.) 930#.

DST #3 3908-3921. 30 Mins.
Rec. 17' mud. IBHP 30#,
IFP 0#, FFP 0#, FBHP (30 min.
30#.

DST #4 3922-3933. 1 hour
Rec. 17' mud. IBHP 1320#,
IFP 0#, FFP 30#, FBHP (30 Min
1140#.

DST #5 3995-4015. 30 Minutes.
Rec. 8' mud. All pressures 0#.

DST #6 4018-4035. 30 Minutes.
Rec. 25' mud. IBHP 30#,
IFP 0#, FFP 0#, FBHP (30 Min.
750#.

RECEIVED
STATE CORPOR. COMMISSION
MAY 24 1958
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK:

I, Earl M. Burch, president of Burch Drilling Co., Inc. being duly sworn on
oath, state: That I have knowledge of the facts, statements and matters herein con-
tained and that the same are true and correct.

Earl M. Burch
Earl M. Burch

Subscribed and sworn to before me this 23rd day of May, 1958.

Garry Harrison
Notary Public



PLUGGING
FILE SEC. 28 T. 9. R 25W
BOOK PAGE 100 LINE 32