

15-065-00323-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 28 Twp. 9S Rge. 25W (EX) (W)

Location as "NE/CNWxSWx" or footage from lines SW SW SW

Lease Owner Anschutz Drilling Company

Lease Name Bollig Well No. 1

Office Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-28-19-53

Application for plugging filed 5-28-19-53

Application for plugging approved 5-28-19-53

Plugging commenced 5-28-19-53

Plugging completed 5-28-19-53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	231'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set at 220' with 15 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Anschutz Drilling Company

Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler

Union Nat'l Bk Bldg., Wichita, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 53

My commission expires May 2, 1956

24-2675-5 2-52-20M



Notary Public.



PLUGGING
FILE SEC 28 T 9 R 25W
BOOK PAGE 105 LINE 4

STATE CORP COM
6-17-53

CONSERVATION

DRILLER'S LOG

Anschutz Drilling Company
 #1 Bollig
 SW SW SW - 28-9S-25W
 Graham County, Kansas

<u>FROM</u>	<u>TO</u>	
0	50	Sand & surface clay
50	160	Surface clay
160	1080	Shale & shells
1080	1263	Shale
1263	1535	Shale, sand & pyrite
1535	1575	Sand & pyrite
1575	1630	Red bed & shale
1630	1665	Anhydrite
1665	1725	Red bed
1725	2192	Red bed & shale
2192	2232	Anhydrite
2232	2325	Pyrite, shale, shells & red bed
2325	2640	Shale & shells
2640	3628	Lime & shale
3628	3967	Lime
3967	4010	Lime & shale
4010	4085	Lime
4085	4155	Lime & shale
4155	4228	Lime
4228	4341	Lime & shale
4341	4382	Chert & lime
4382	4450	Lime
	4450	ROTARY TOTAL DEPTH D&A

COMMENCED: 5-12-53
 COMPLETED: 5-28-53

CASING RECORD

Set 8-5/8" surface casing at 231'
 with 175 sacks cement.

ELEVATION: 2554 RB

TOPS

Heebner 3778
 Lansing 3801
 Base Kansas City 4059
 Mississippi chert 4341
 Mississippi lime 4392

DRILL STEM TEST

3790-3873, open 1 hour, recovered
 55' salt water, BHP 1200#
 closed 30 minutes.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Bollig located SW SW SW of Section 28-9S-25W, Graham County, Kansas.

ANSCHUTZ DRILLING COMPANY

BY:

Leon L. Mehler
 Leon L. Mehler

Subscribed and sworn to before me this 9th day of June, 1953.

My Commission Expires: May 2, 1956



Jacqueline Linn
 Notary Public

RECEIVED
 STATE CORPORATE COMMISSION
 JUN 17 1953
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 28 T 9 R 25W
 BOOK PAGE 105 LINE 4