

STATE OF ~~OKLAHOMA~~ NSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

RT-KCC
API NUMBER 15-065-2075 ⁰-0001

LEASE NAME Kuhn A

WELL NUMBER 5W

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

1320 Ft. from S Section Line

1320 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 34 TWP. 9S RGE. 25 (X) or (W)

ADDRESS P. O. Box 26100

COUNTY Graham

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 6/6/75

Character of Well Input

Plugging Commenced 11/18/93 ¹⁰ _{RT KCC}

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/19/93 ¹⁰

The plugging proposal was approved on 10/19/93 (date)

by _____ (KCC District Agent's name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation LKC/Toronto Depth to Top 3808 Bottom 4032 T.D. 4070

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
LKC/Toronto	Oil	3808	4032	8 5/8	1407	
				5 9/16	4070	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

RIH w/ 2 7/8 tbq. to btm. (4046) pumped 125 sxs Standard w/1/4#sk Flocele. POOH w/ 34 jts. Pumped 65 sxs 65/35 w/10% gel & 1/4# sk Flocele & 100# hulls. POOH w/32 jts of tbq. Pumped 65 sxs 65/35 w/10% gel. 1/4#sk Flocele & 100 # hulls. POOH w/ 32 jts. 2 7/8 tbq pumped 3495 sxs 65/35 w/10% gel w/1/4# sk Flocele & 450# hulls. RIH w/sinker bar on sandline & tagged cmt @ approx 1000',

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service License No. 5866

Address 505 W. Commercial, Logan, Ks 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Ledlow RECEIVED
STATE CORPORATION COMMISSION
12-06-93

(Address) P. O. Box 26100, OKC, OK 73126-0100 DEC 06 1993

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 93

Sammy R Padella
Notary Public CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: 8-21-96

Continuation of plugging information:

RIH w/strip shot and tagged cmt @ 925, Pulled up to 915' and shot 2 holes in csq. Fluid was 350' from surface. Hooked up Howco and pumped 25 bbls fresh wtr w/full returns. Mixed & pumped 175sks 65/35 w/10%gel & 1/4# sks flocele down 5 1/2 csq. Circ 10sks cmt to the pit. Closed in the backside and press to 1000#.

