

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. MARKET, ROOM 2078
 WICHITA, KS 67202

WELL PLUGGING RECORD
 K.A.R. -82-3-117

API NUMBER 15-065-20,749 - 0001

LEASE NAME Rome Estate

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

WELL NUMBER 5 W

1420 Ft. from S Section Line
4060 Ft. from E Section Line

LEASE OPERATOR VESS OIL CORPORATION

SEC. 34 TWP. 9S RGE. 25 (E) or (W)

ADDRESS 8100 E. 22nd North, Bldg 300; Wichita, KS 67226

COUNTY Graham

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed 6/10/1975

Character of Well Input

Plugging Commenced 9/18/2000

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/18/2000

The plugging proposal was approved on 9/15/2000 (date)
 by Carl Goodrow - verbal (KCC District Agent's Name)

Is ACO-1 filed? na If not, is well log attached? yes

Producing Formation Toronto, Lt Depth to Top 3778 Bottom 4004 T.D. 4050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1426	none
				5 1/2	4050	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged and Abandoned as follows: Ran tbg and spotted 50 sx 60/40 poz w/10% gel at 3550'. Spotted 50 sx cement at 2950'; Spotted 50 sx cement at 2350'; Spotted 75 sx cement w/500# hulls at 1750'; Spotted 80 sx cement at 1150' and cement circulated to surface. TOH w/tbg. Filled 5 1/2" casing w/ 15 more sx cement. Tied onto 8 5/8" x 5 1/2" annulus and pumped 40 sx cement - 450#. Approved by Carl Goodrow w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing

RECEIVED
 STATE CORPORATION COMMISSION
 License No. 9-27-00
 SEP 27 2000

Address Box 31; Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss. Wichita, Kansas

(Employee of Operator) or (Operator) of
 above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this

8100 E - 22nd St. N. Wichita, KS 67226

20th day of Sept 2000

Michelle D. Henning
 Notary Public

My Commission Expires:

Form CP-4
 Revised 05-88



(Handwritten initials)