

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-00635-0001
API NUMBER 15-NA

LEASE NAME Rome

WELL NUMBER 1-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

3360 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Company, Inc.

SEC. 27 TWP. 9 RGE. 25 (X) or (W)

ADDRESS 250 N. Water, Suite 300 Wichita, KS 67202

COUNTY Graham

PHONE# (913) 674-2103 OPERATORS LICENSE NO. 30606

Date Well Completed N/A

Character of Well Injection

Plugging Commenced 12/9/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/9/93

The plugging proposal was approved on 4/24/93 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? _____

Producing Formation LKC Depth to Top 4039 Bottom 4076 T.D. 4112

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Water	4039	4076	8 5/8	296	0
				5 1/2	4112	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pumped down 5 1/2" casing w/400 sx 60-40 Poz, 8% gel, 500# hulls.

Max PSI 500 psig, ISTP 200 psig. Checked 8 5/8, pressured to 300 psig, held.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor _____ License No. 12-14-93

Address _____ CONSERVATION DIVISION
Wichita, Kansas


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF _____ COUNTY OF _____, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Lester

(Address) P.O. 130 HILL CITY, KS



AND SWORN TO before me this 73 day of Dec, 19 99

Donna Gerstner
Notary Public

My Commission Expires: June 24, 1997