

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 27 TWP. 9S RGE 25W E/W
Location as in quarters or footage from lines:
C S/2 NE

Locate Well
correctly on above
Section Platt.

Lease Owner Nickelson Oil Operations
Lease Name Spies #1 Well No. _____
Office Address Rt. 1 Box 76 Hill City, Ks. 67642
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2-10-82
Plugging completed 2-26-82
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation _____ Depth to top _____ bottom _____ T.D. 4060' 4135'
Show depth and thickness of all water, oil and gas formations. RT
KCC

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"		none
				4-1/2"		2797'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3050' and ran 4 sacks cement. Shot casing @3000' and
2802'. Pulled a total of 71 joints of pipe. Plugged well with 4 sacks hulls, 12 sacks
gel, 70 sacks cement, 1 sacks hulls, plug, 13 sacks gel, 70 sacks cement, 50/50 pos,
2% gel, 3% cc. Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1982
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176, Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 82

My Commission expires:



Irene Hoover
Notary Public.