


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 27 Twp. 9 Rge. 25 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
Se/4

Lease Owner Nickelson Oil Company
Lease Name SPIES "A" Well No. 1
Office Address R. R. #1, P.O. Box 76, Hill City, Kans
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed Feb. 20 1980
Application for plugging filed (verbally) Feb. 20 1980
Application for plugging approved (verbally) Feb. 20 1980
Plugging commenced Feb. 20 1980
Plugging completed Feb. 20 1980
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4145'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4145'
Set 1st plug at 1100' with 70 sacks
2nd plug at 280' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 6:00 a.m., 02-20-80.

3-3-80
3-3-80


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 80



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Nickelson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Spies "A" #1
 LOCATION: SE/4, Section 27-9-25
 Graham County, Kansas
 SPUD DATE: February 13, 1980
 COMPLETION DATE: February 20, 1980

0	290	Top soil, sand and shale
290	600	Shale
600	2221	Sand and shale
2221	2395	Anhydrite and shale
2395	2935	Shale
2935	3210	Lime and shale
3210	3580	Lime
3580	3725	Lime and shale
3725	4145	Lime
	4145	Rotary Total Depth

Spud hole at 7:30 p.m., February 13, 1980. Drilled 290' of 12 1/4" hole. Ran 7 joints of 8-5/8" new 20# casing. (Talley 281.64'). Set at 289.50' with 215 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 2:00 a.m., February 14, 1980.

T.D. 4145'. Set 1st plug at 1100' with 70 sacks, 2nd plug at 280' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:00 a.m., February 20, 1980.

SAMPLE TOPS:

Anhydrite 2221'
 B/Anhydrite 2261'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SPIES "A" #1, SE/4, Section 27-9-25, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 27th day of February, 1980.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

RECEIVED
 CONSERVATION COMMISSION
 MAR 3 1980