


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ellis County, Sec. 28 Twp. 11S Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines SE - SE - NE
Lease Owner Great Bend Pipe & Supply
Lease Name Wasinger Well No. 5
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 2-2 19 60
Plugging completed _____ 2-5 19 60
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1311	None
				4 1/2	3600	2422.32


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3520' - dumped 10 sacks of cement - pulled casing to 500' - pumped in 13 sacks of mud and 20 sacks of cement - pulled pipe to 180' - pumped in 20 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
2-23-1960
FEB 23 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 154 Ellinwood, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Nathan Meltzer
P.O. Box 191 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of February 19 60
Anne Meltzer
Anne Meltzer Notary Public.
My commission expires March 30, 1961

15-051-05225-00-00

SHELL-LARIO-F. S. WASINGER #5
SE SE NE Section 28-11S-18W
371'SL & 330'EL of NE $\frac{1}{4}$
Bemis-Shutts Field
Ellis County, Kansas

Casing Record

8 5/8" cem 1311 with 360 sax
4 1/2" cem 3600 with 200 sax; perforated 3539-47.

- 0 - 75 surface
- 390 shale & lime
- 597 shale, redbed & sand
- 805 shale & sand
- 960 sand
- 1050 redbed, shale & pyrite
- 1302 redbed & pyrite
- 1314 anhydrite
- 1425 shale & red bed
- 1856 shale
- 1945 shale & lime
- 2081 shale, salt & lime
- 2185 shale
- 2260 shale & lime
- 2302 lime
- 2588 shale & lime
- 2715 lime & shale
- 2794 shale & lime
- 2900 shale
- 3019 shale & lime Top Topeka 2964
- 3575 lime Top Lansing-Kansas City 3226
- Top Simpson Dolomite 3518
- Top Simpson Shale 3523
- Top Arbuckle 3538
- 3602 lime & chert
- 3602=3601 SLC T.D.
- 3563 P.B.

RECEIVED
STATE COMMISSION
2-2-1960
FEB 2 1960
CONSERVATION DIVISION
Wichita, Kansas

Initial production 10-5-48: I.C. 9618 BO, no water.
Date of last production: 4-29-59 - Pumped 3 BO & 24 BW 24 hours.

L. Byers 2-1-60