


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-20705-00-00

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County, Sec. 10 Twp. 11S Rge. 18W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner A. Scott Ritchie  
Lease Name Meistrell "A" Well No. 1  
Office Address 412 Union Center Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 29 19 70  
Application for plugging filed December 29 19 70  
Application for plugging approved December 29 19 70  
Plugging commenced December 29 19 70  
Plugging completed December 29 19 70  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3177' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	251'	8 5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug: 420'/50 sacks cement  
240'/25 sacks cement  
40'/10 sacks cement


RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.  
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
D. L. Hellar, President of Hellar Drlg. Co. Inc. (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) D. L. Hellar D. L. Hellar, President  
339 Union Center Bldg., Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 31st day of December, 19 70



Catherine Darcey  
Catherine Darcey - Notary Public.

My commission expires March 25, 1972

15-051-20705-00-00

DRILLER'S LOG

COMPANY: A. Scott Ritchie, 412 Union Center Bldg., Wichita, Kansas 67202  
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202  
 LEASE: #1 Meistrell "A"  
 LOCATION: SE SE SW 10-11S-18W, Ellis County, Kansas  
 COMMENCED: December 21, 1970  
 COMPLETED: December 29, 1970  
 CASING: Set 8 5/8" Surface Casing @ 251'/225 sacks cement

0-220	Shale & Rock
220-251	Shale
251-460	Shale & Red Bed
460-595	Sand & Shale
595-1165	Shale & Sand
1165-1180	Shale
1180-1221	Anhydrite
1221-1425	Shale & Shells
1425-1760	Shale - Red Bed & Salt
1760-1965	Shale & Lime
1965-2170	Lime & Shale
2170-2226	Lime
2226-2970	Shale & Lime
2970-3071	Lime & Shale
3071-3140	Lime
3140-3177	Lime (L.K.C.)
3177	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 1-5-1971  
 JAN 5 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

D & A

STATE OF KANSAS        )  
                               ) SS  
 COUNTY OF SEDGWICK    )

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Meistrell "A", located in SE SE SW 10-11S-18W, Ellis County, Kansas as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*  
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 31st day of December, 1970.



*Catherine Darcey*  
 Notary Public - Catherine Darcey

My Commission Expires: March 25, 1972.