


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-04724-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 28 Twp. 11 Rge. 18 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
Lease Owner Simon Lebow
Lease Name Truan Well No. 1
Office Address 608 Oil Capital Bldg. Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 14, 19.50
Application for plugging filed May 13, 19.50
Application for plugging approved 19.
Plugging commenced May 14, 19.50
Plugging completed May 14, 19.50
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3575 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Loaded hole with mud, set first plug 250 feet, dumped 15 sacks of cement, loaded within 35 feet of top, set second plug, then dumped 10 sacks of cement.

5-16-1950
MAY 16 1950


(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Raymond & Lebow Drilling Company Inc.
Address 202 Bissantz Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Francis M. Raymond (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Francis M. Raymond*
202 Bissantz Bldg. Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15th day of May, 19.50
My commission expires May 18-1952
Gene W. [Signature]
Notary Public



22-7877-s 4-49-10M

PLUGGING
FILE SEC 28 T 11 R 18 W
BOOK PAGE 5 LINE 40

Simon Lebow
608 Oil Capital Bldg.
Tulsa, Oklahoma

NE 1/4-NW 1/4-28-14-18W
County, Ellis
State, Kansas

Truan No.1

Production D & A.

Comm. 5-1-50
Comp. 5-15-50

Total Depth 3575

Casg. 8 5/8" Cem.

Cellar	0	5
Surface Soil & Clay	5	40
Surface Sand & Shale	40	150
Shale	150	260
Lime, Shells & Shale	260	375
Shells & Shale	375	400
Blue Shale (Stickey)	400	440
Sandy Shale	440	460
Shale Stickey	460	490
Red Bed	490	545
Red Bed & Shale	545	575
Sandy Shale	575	630
Shale	630	675
Sand	675	700
Sandy Shale	700	760
Sand & Gravel	760	940
Shale	940	980
Shells & Shale	980	995
Shale	995	1025
Red Bed	1025	1262
Chalk	1262	1266
Anhydrite	1266	1330
Red Bed & Shale	1330	1390
Salt	1390	1540
Shale & Lime	1540	1915
Lime	1915	1995
Lime & Shale	1995	3460
Shale & Hard Lime	3460	3508
Cherty Lime and Shale	3508	3540
Lime & Shale	3540	3575

Total Surface Depth 1275'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

RAYMOND & LEBOW DRILLING COMPANY INC.

BY James M. Raymond

State of Kansas)
) SS
County of Sedgwick)

5-16-1950

Subscribed and sworn to before me a Notary Public, in and for Said County and State this 15th. day of May, 1950.

Y. Newberry
Notary Public

My commission expires May 14, 1952

PLUGGING
FILE SEC 287 11 R 18W
BOOK PAGE 5 LINE 40