


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-051-05223-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 28 Twp. 11 Rge. 18 / (H) / W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CNE SE NW

Lease Owner Gulf Oil Corporation

Lease Name I. Truan Well No. 2

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 1 19 49

Application for plugging filed Verbal 19

Application for plugging approved October 30 19 52

Plugging commenced November 4 19 52

Plugging completed November 10 19 52

Reason for abandonment of well or producing formation

Not economical to produce.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3579' Bottom 3594' Total Depth of Well 3594' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"OD	1313'	NONE
				5 1/2"OD	3581'	2924'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock from 3594'-70', dumped 4 sacks of cement at 3570'. Mudded hole to 300', set rock bridge. Dumped 15 sacks of cement on bridge. Mudded to 35' of surface. Capped with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Morgan Pipe Pulling Service
Address Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
W. H. Duley (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley

Box 544, Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of November, 1957

My commission expires April 14, 1956

28-5091-8 8-50-10M

RECEIVED
STATE CORPORATION COMMISSION
11-14-1952
NOV 14 1952

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28 T 11 R 19
BOOK PAGE 55 LINE 42



15-051-05223-00-00

WELL NO. 2 LEASE Ida Truen COMPANY Gulf Oil Corporation A.F.E. 3909
 DATE—DRILLING BEGAN 2-14-49 WELL COMPLETED 4-1-49 FIRST PRODUCTION 3-13-49
 SAND RECORD Arbuckle 3579' TOTAL DEPTH 3594'
 P. B. from 3597'
 INITIAL PRODUCTION OIL: "p" 32 barrels On State test
 WATER: 60 barrels

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8"	24	8R	A	*	1313'	525			1313'
5-1/2	15.5	8R	**	Smls	3581	100			3581

S— 28 T— 11S R— 18W

				1656'	SNL
				& 330'	WEL
			0		NW/4
				Ellis	
				County	
				Kansas	

DISTANCE H: Top Collar on 5-1/2" is 6" below rotary bushing.

ELEVATION— 2031'

ACIDIZED: With 500 gallons 3-14-49
 ACIDIZED: With 1000 gallons 3-21-49

FORMATION RECORD:

	FROM	TO
Clay	0'	300'
Shale and shells		385
Shale		415
Shale and shells		570
Shale, shells and red bed		725
Shale and red		1105
Lime, sandy		1145
Shale, shells and red bed		1165
Red bed and shale		1290
Lime, Chalky		1300
Anhydrite		1385
Shale and shells		2100
Lime		2145
Lime and shale		2860
Lime		2920
Lime and shale		3000
Lime		3520
Chert and lime		3570
Lime		3585
Deepened with cable tools to		3597
TOTAL DEPTH		

10-30-1952

ED:WF

4-25-49

PLUGGING
 SEC 28 T 11 R 18W
 BOOK PAGE 55 LINE 42