


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-19230-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 28 Twp. 11S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines NE - SE - NE
Lease Owner Great Bend Pipe & Supply Co.
Lease Name Wasinger Well No. 2
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8 - 31 19 58
Plugging completed 9 - 2 19 58
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1345	None
				4 1/2	3628	2520.25

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3550' - dumped 3 sks cement - mudded hole to 550' - set 10' rock bridge - dumped 20 sks cement - mudded to 200' - set 10' rock bridge - dumped 20 sks cement - mudded to 35' - set 10' rock bridge - dumped 10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
10-2-1958
OCT 2 1958
CON. DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Nathan Meltyer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltyer
Box 191 - 2th. Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October 19 58

My commission expires 3/30/61
Notary Public.



PLUGGING
FILE SEC 28 T 11 R 18W
BOOK PAGE 125 LINE 34

SHELL-LARIO-F. S. WASINGER #2
NE SE NE Section 28-11S-18W
Burnett, S.W. Field
Ellis County, Kansas

Casing Record

8 5/8" cem 1345 with 400 sax; circulated.
4 1/2" cem 3628 with 200 sax; perforated
3573-3583. Centralizers at 3611, 3581,
3551, 3305 & 3114.

- 0 - 452 shale
- 512 shale & lime
- 661 shale
- 770 sand
- 840 lime & shale
- 995 sand
- 1005 shale & lime
- 1162 shale & red rock
- 1330 red bed
- 1336 red bed & pyrite
- 1343 shale & red bed
- 1383 anhydrite
- 1546 red rock
- 1800 red bed, sand & shale
- 1938 shale & lime streaks
- 2035 shale & lime
- 2187 salt, sand, shale
- 2233 shale & lime
- 2302 lime & shale streaks
- 2369 shale
- 2468 lime & shale
- 2574 lime streaks & shale
- 2890 lime & shale
- 2990 shale
- 3034 lime & shale
- 3059 lime
- 3123 shale & lime
- 3157 lime
- 3237 lime & shale
- 3489 lime
- 3531 lime & shale
- 3556 shale & chert
- 3560 conglomerate
- 3564 dolomite
- 3574 shale
- 3581 dolomite
- 3583 shale, cherty, sandy
- 3629 dolomite T.D.
- 3615 P.B. (cement)

Formation Tops

- Topeka 3001
- Lansing-Kansas City 3265
- Sooy 3523
- Simpson Dolomite 3559; Shale 3563
- Arbuckle 3573

Initial Production: I.C. 5654 oil 0 water 8-3-48
Last Production: 4-4-58

8-28-1958
10823

PLUGGING	
FILE SEC.	28T 11 R 18W
BOOK PAGE	125 LINE 34