

15-051-04691-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County.. Sec. 4 Twp. 11S Rge. (E) 18W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Martin "C" Well No. 2
Office Address P. O. Box 97, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-7-60 19
Application for plugging filed 11-7-60 19
Application for plugging approved 11-7-60 19
Plugging commenced 11-7-60 19
Plugging completed 11-7-60 19
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3655 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/3 sack of hulls, wooden plug set at 500' /
Mixed 20 sacks cement through drill pipe.

1/3 sack of hulls, wooden plug set at 180'.
Mixed 15 sacks cement through drill pipe.

1/3 sack of hulls, wooden plug set at 40'.
Mixed 10 sacks cement through drill pipe.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address P. O. Box 97, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover
V. Richard Hoover, President

(Address)



SUBSCRIBED AND SWORN to before me this 7th day of November, 19 60

Helen E. Fischer
Helen E. Fischer Notary Public.

15-051-04691-00-00

WELL LOG

Chief Drilling Co., Inc.
P. O. Box 97
Great Bend, Kansas

#2 Martin "C"
SE SE SW Sec. 4-11S-18W
Ellis County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 10-27-60
Completed: 11-7-60
D & A

Casing Record: 8-5/8" at 230' with 175 sacks HA5 Quickset Cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Post Rock & Shale	0	230'	2064' Gr.
Shale & Sand	230'	800'	2066' D.F.
Sand	800'	925'	2069' K.B.
Shale with Sand Streaks	925'	1140'	
Redbed & Shells	1140'	1190'	
Shale & Shells	1190'	1385'	
Anhydrite	1385'	1418'	
Shale & Shells	1418'	1585'	
Shale & Lime	1585'	2360'	
Lime & Shale	2360'	3047'	
Lime	3047'	3269'	
Lime & Shale	3269'	3309'	
Lime	3309'	3532'	
Shale & Lime	3532'	3565'	
Chert	3565'	3601'	
Shale, Dolomite, & Sandy Shale	3601'	3630'	
Dolomite	3630'	3655'	
Total Depth	3655'		

<u>FORMATION TOPS</u>	
Anhydrite	1385' (+684)
Topeka	3047' (-978)
Heebner	3269' (-1200)
Toronto	3286' (-1217)
Lansing	3309' (-1240)
Base Kansas City	3532' (-1463)
Conglomerate	3565' (-1496)
Simpson	3601' (-1532)
Arbuckle	3630' (-1561)

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE SE SW Sec. 4-11S-18W, Ellis County, Kansas to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

11-8-1960

CONSTITUTION OF...
Wichita, Kansas

Subscribed and sworn to before me this 7th day of November, 1960.

My commission expires October 3, 1964.

Helen E. Fischer
Helen E. Fischer, Notary Public

