


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-19229-00-00

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Ellis County, Sec. 28 Twp. 11S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines NE - NE - NE

Lease Owner Great Bend Pipe & Supply

Lease Name F. S. Wasinger Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_

Plugging commenced \_\_\_\_\_ August 28 19 58

Plugging completed \_\_\_\_\_ August 30 19 58

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1278	None
				4 1/2	3612	2569.81


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3500' - dumped 3 sks cement - mudded hole to 550' with fresh water and Jel Mud - set plug and 10' rock bridge - dumped 20 sks cement - mudded hole to 200' - set 10' rock bridge - dumped 20 sks cement - mudded to 35' - set 10' rock bridge - dumped 10 sks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-24-1958  
SEP 24 1958  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company License # 236  
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Nathan Meltzer

Box 191, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 58

Nathan Meltzer Notary Public.

PLUGGING  
FILE SEC 28 T 11 R 18 W  
BOOK PAGE 125 LINE 33

15-051-19229-00-00

SHELL-LARIO-F. S. WASINGER #1  
NE NE NE Section 28-11S-18W  
Burnett, S.W. Field  
Ellis County, Kansas

Casing Record

8 5/8" cem 1278 with 600 sax; circulated.  
4 1/2" cem 3612 with 400 sax; perforated 3513-19  
& 3521-25. Centralizers at 3607, 3567,  
3527, 3487, 3447, 3407, 3367  
& 3327.

0 - 70 surface rock & shale  
150 " " " "  
225 shale  
775 shale & shells  
1000 shale & sand  
1025 shale & red bed  
1081 sand & red bed  
1155 red bed & shale  
1200 red bed  
1265 red bed & shells  
1305 anhydrite  
1320 lime & shale  
1400 red bed & sand  
1525 shale & sand  
2025 shale & shells  
2115 shale, shells & salt streaks  
2720 shale & lime  
2745 shale & shells  
2770 lime & shale  
2800 shale & shells  
2835 shale & lime  
2938 shale & shells  
2944 shale, black  
3110 lime & shale  
3180 lime  
3215 lime, cherty  
3430 lime  
3466 lime & shale  
3495 conglomerate - lime & shale  
3502 dolomite  
3513 shale  
3520 dolomite, shale streak  
3521 dolomite  
3523 dolomite, shale streaks  
3600 dolomite  
3613 dolomite, cherty T.D.  
3572 P.B. (top cement)

Formation Tops

Topeka 2944  
Lansing-Kansas City 3207  
Sooy Conglomerate 3466  
Simpson 3495  
Arbuckle 3513

Initial Production: I.C. 7548 B0, no water 6-23-48  
Last Production: 4-4-58

8-28-1958  
M. E. S. 1958

PLUGGING			
FILE	SEC	20T.11	R18W
BOOK	PAGE	125	LINE 33